

Departmen Permukiman Umum Direktorat Jenderal Sumber Daya Air

CTI Engineering International Co., Ltd. Consulting Engineers

Bawakaraeng Urgent Sediment Control Project (The Most Urgent Components)

August 2005

The Collapse

- On March 26, 2004, Mt. Sorongan (EL.2,541m) in the caldera of Mt. Bawakaraeng Collapsed.
- The estimated collapsed volume: 200 300 mil. cum.
- Damage: 32 people death and missing, 635 cows losing, Houses and elementary school in Lengkese village and about 1,500 ha. of agricultural land buried;

The damages expected:

- The riverbed aggradations and loss of properties along the river such as paddy fields;
- Sedimentation of Bili-Bili Dam (; and
- Secondary disaster due to debris flow (Carrying away of Daraha Bridge, Existing bank erosion etc.).





Collapsed Mountain

Before the Collapse As of July 2002

Mt. Sorongon

Mt. Bawakaraeng

After the Collapse As of March 2004



Collapsed Mountain (Aerial Photos)



August 1993

July 2004

Collapsed Area (As of April 8, 2005)



After Collapse – at Lengkese (March 26, 2005)

Evacuation of Village People





Buried Paddy Field (Parangkeke)

Development of Gully

April 8, 2004

June 20, 2004



January 22, 2005

September 27, 2004

December 9, 2004



February 14, 2005

9

Damages – Debris Flow



Sand Pocket Dam No. 5



The left abutment of SP No. 5 was completely buried by debris.

At the downstream of SP No.5, village people start cultivating.

Jeneberang River Channel

Paddy fields along the river were buried. The damage expands day by day.

March 26, '05





Evacuated Houses along the River (Bonto-Jai)

March 26, '04





Damages – Sedimentation of Bili-Bili Dam





Sedimentation at Upstream of the Bili-Bili Reservoir

at present, the sediment volume is estimated at 10mil m3 while the design sediment volume is set at 29mil. m3.



Raw Water Turbidity at Somba-Op Water Purification Plant

During rainy season in '04 to '05, the operation and supply water were stopped for 22days or 350hrs. in total due to the sediment content.

Damages – River Structures

Sand Pocket No. 4



Daraha Bridge

Daraha Bridge was flushed out by debris flow on 14 April 2005. Trans 13,000 village People has been affected.







The Project

Bawakaraeng Urgent Sediment Control Project

Objectives of the Project

To protect public assets such as Bili-Bili dam and the farmlands and properties along the river;

To mitigate the secondary disaster due to the debris flow,

To realize sustainable Sabo works and sand management, and

To improve the social welfare in the affected area.

Counter Measures

Following countermeasures will be provided to achieve the objectives in accordance with the **ISDM** concept:

Structural Measures

- Construction of Sabo Dams;

Rehabilitation of existing structures
 (Road, bridge and Sand Pocket Dam No. 4);
 Removal of River Deposit at Sand Pocket Dams and Bili-Bili Reservoir.

Nonstructural Measures

 Urgent inspection for prediction of further collapse
 and occurrence of debris flow;
 Providing forecasting and warning system against
 the debris flow.

Sediment Control plan

Sediment Balance up to 2009



General Map of the Project





Sabo Dam Plan: Profile



Sabo Dam Plan: Plan



The Most Urgent Components Selection Concepts

For the early implementation of the works, the Consultant was selected under direct appointment. But the scope of works were limited to the Most Urgent Components which were selected in accordance with following concepts:

- The works will affect the peoples' lives and their daily activities.
- The works related to the sediment control and must be conducted within this year to catch up the proposed schedule.

Scope of Works

the Most Urgent Components (1) Study Components

- Urgent Investigations (Data Collection, Survey for Further Collapse);
 - Preparation of hazard map and monitoring, warning and evacuation systems;
- Periodical survey of river and reservoir and its analysis;
- (2) Environmental and Regional Development Components
- Establishment of PAFs' Participatory Process to the Project;
- Environmental Monitoring;
- (3) Structural Components
- Excavation of Riverbed Deposit to be conducted in 2005 and 2006;
- Construction of Series of Sabo Dams No. 7 to be constructed in 2005 and 2006;
- Establishment of Telemetry System;

Proposed Additional Works

Works should be conducted immediately

- Design of Daraha Bridge.
- Rehabilitation of Sand Pocket Dam No. 4.
 Sediment Flashing for Bili-Bili Dam.
- Works to be conducted in Stage II
 - Succeeding works of MUC
 - Construction of Daraha Bridge
 - Regional Development
- Works to be conducted in future
 - Reservoir Sedimentation Control Measures.
 - Surface Water Intake System.
 - Watershed Management Plan of the JRB.

Proposed Additional Works

Proposed Additional Sediment Control Measures



Implementation Schedule

		' 04	'0 5	"()6	' 0	7	°C	8	6	09		61	0
			apse (Ma Apprais APledo L/A	ar. '04 al (Oc ge (Ja A (mai	1) t. 04 n. '05 . '04)								
E/S for MUC/Stage II			M	UC			St	age	11					
1. Riverbed Excavation Works	Unc	ler APB	N											
2. Sabo Dams Construction														
3. Establishment of Telemetry System														
4. Daraha Bridge Construction												••••••		
5. Rehabilitation of Structures														
6. Regional Development Works														
7. Environmental Monitoring												Up	to	2012
8. Urgent Survey/Long Term Plan			Ur	gent	Surve	у				on	gТ	ern	۱PI	an
9. Sabo Community Support														
												2	5	

Present Activities Construction Works

Construction of Sabo Dam No. 7-1

- Dec. 2004 - Design
- Tender May - Jul. 2005
- Jul. 2005 Oct. 2005 - Construction
- Telecommunication System
 - Jun. August 2005 - Design
 - Sep. Dec. 2005 - Tender Jan. - Oct. 2006
 - Construction

26

Present Activities Urgent Survey

Starting from June 2005

- Site Investigation in & around the Caldera.
- Data Collection
 - Related Reports/Topographic Maps
 - Rainfall Data from DCO/DINAS;
 - Turbidity of Raw Water from PDAM & PLN;
 - Debris Flow & Rainfall records from Sabo Communities.
- Evaluation of Collapse Mass & Sediment Movement through Map/Aerial Photo Readings.
- Geological Evaluation
 - Geological
 - Verification of Mechanism of the Collapse;
 - Evaluation of further collapse.

Present Activities Subcontract Works

Topographic Survey

- Aerial photo & Ortho-photo mapping
- River Cross-sectional Survey
- Reservoir echo-sounding
- Topographic survey at Daraha Bridge
- Material & Geological Investigation
 - Riverbed Material Survey
 - CSG & ISM Trial Mix.
 - Geological Survey at Daraha Bridge
- The environmental monitoring for the construction works
 Assistance works of the activities of Sabo Communities in Jeneberang

Activities of Sabo Community

Monitoring of Sediment Movement and Debris Flow.
 Monitoring of Rainfall at Panaikang.
 Public Avareness of Sediment Disaster.
 Preparation of Hazard Map applying the PRA Process;
 Establishment of Evacuation Center;
 Indication of Hazardo
 Emergency Bull of Works Zene;

AND A REALIST

Support of Local Economic Activity - Training of Production of Concrete Paven - Nourish of young trees, etc.;

Block;

